



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

NO.CEO/RE(O)/CIVIL/6917-21

Dated:- 18 / 7 - /2022.

1. M/S Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
2. M/S P.C Chawala & Co, House No. E-191 Gulstan-e-sajjad, Qasimabad Hyderabad
3. M/S Fayyaz Traders, 19/B Mir Fazal Town Latifabad, Hyderabad
4. M/S S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
5. M/S Techno-Pak Construction Co, H. A #4/09 Mehran University Housing Society District Jamshoro

QUOTATION

SUBJECT: **REPAIR & MAINTENANCE AND FLOOR OF QUARTER NO. D-10, D-115 & D-249 AT RESIDENTIAL COLONY TPS JAMSHORO.**

Quotations for the above subject work are hereby invited from your company/ firm on percentage rate basis on the following terms and conditions.

SR.No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Removing cement Plaster	Sqm	127.21	24.38	3101.38
2	Cement plaster (1:4) upto 6.00 Meter Height 13mm thick	Sqm	127.21	203.67	25908.86
3	White Washing 02 coats	Sqm	278.08	29.73	8267.32
4	Colour Washing tow coats	Sqm	568.77	13.48	7667.02
5	Distempering Two Coats	Sqm	783.53	64.41	50467.17
6	Panting doors and windows any type Two coats.	Sqm	167.15	183.10	30605.16
7	Painting Shases fan light glazed or gauze doors and windows any type two coats	Sqm	66.90	107.58	7197.10
8	Glazing with pans 454 to 512 gm use with putty	Sqm	6.69	732.46	4900.16
9	Topping of cement concrete 1:2:4 i/c surface finishing and dividing into panels 40mm thick	Sqm	118.90	365.64	43496.53
10	Glass strips for dividing the floor into panels 40mm thick	Rm	195.06	80.05	15614.55
11	Providing / fixing laminated board shutter for ward robe as per drawing	Mtr	10.37	2523.87	26172.53
12	½" x1" x 1/16" for wardrob Almirah i/c cutting, bending, welding etc or labour & material as per drawing	Mtr	14.94	485.20	7248.89
13	Providing & fixing steel tublar frame 1-1/2"x1"x1/16" for kitchen shutter etc, all labour & material as per drawing	Mtr	2.74	227.30	622.80
14	Cement concrete plain i/c placing, compacting, finshing & curing complete (i/c screening & washing of stone aggregate(with shuttering Ratio: 1:2:4	Mtr	0.35	6343.62	2220.26
TOTAL RS.					2,33,490.00

Add: Contractor Premium _____% above/below Rs. _____


Total Rs. _____

SPECIAL CONDITIONS

- 01- The Quotation shall be received on 01-8-2022 at 12:00 in Tender / Quotation box at office of CE/TD and Opened at 12:30 on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

ENQUIRY**DUE FOR OPENING ON**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 30 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 1500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill


Resident Engineer (O)
(GENCO-I) JPCL, Jamshoro.

Cc.to:

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.