



JAMSHORO POWER COMPANY LIMITED (Genco-I)

No. CEOJ/R.E(M)/T-799/20/ME(B)/

6719

Dated: 11-08-2020

JPCL INVITING TENDER NOTICE

Subject: THE WORK OF DISMANTLING OF EXISTING DAMAGED CLADDING AND INSULATION PADS AT THE OUTLET OF AIR PRE-HEATER 1A & 1B SIDE INSTALLATION OF NEW G.I SHEETS AND CERAMIC WOOLS AT THE AIR PRE-HEATER 1A & 1B AND TOWARD THE FLUE GAS DUCT AREA AND ALIGNED NAKED STEAM PIPES AROUND THE AIR PRE-HEATER 1A & 1B & FLUE GAS DUCT REPAIRING OF BOILER OF UNIT NO.1 TPS, JAMSHORO (T-799/20/ME(B))

Tender on Lump Sum basis for the subjected work as detailed below are hereby invited from your firm on the terms and condition detailed below:-

S.N	Description	Unit	Qty
1	Providing and installation / fixing of MS scaffolding outside of Air pre-heater 1A & 1B at the Height of 20 to 30 meter for dismantling and installation work	Sqm.	350
2	Dismantling and installation of existing damaged cladding (G.I sheets) and insulation by riveting at Air Pre-heater 1A near FD Fan	Sqm.	20
3	Dismantling and installation of existing damaged cladding (G.I Sheets) and insulation by riveting of Air pre-heater 1B near F.D	Sqm.	30
4	Dismantling and installation of existing damaged cladding (G.I Sheets) and insulation by riveting at the outside of Air pre-heater	Sqm.	30
5	Removal of damaged G.I sheets and insulation pads and installation by riveting at the inlet centre of Air pre-heater 1A & 1B	Sqm.	103.89
6	Removal of damaged G.I Sheets and insulation pads and installation by riveting at the inlet (Top) of Air pre-heater 1A & 1B	Sqm.	119.42
7	Removal of damaged G.I sheets and insulation pads and installation by riveting at the inlet side wall of Air pre-heater 1A & 1B	Sqm.	88.91
8	Dismantling and installation of existing damaged cladding (G.I Sheets) and insulation at the outlet of Air pre-heater 1A & 1B front and back side	Sqm.	332.23
9	Inlet flue gas top and centre duct of Air pre-heater 1A & 1B	Sqm.	329.91
10	Dismantling, fabrication, erection, installation and welding M.S new plates size 4.5mm thickness and angle iron 100 x 100 x 6mm at damaged portion of flue gas duct from outlet air pre-heater both sides to stack, the work complete in all respect as per satisfaction of engineer incharge.	Sqm.	84.01

01. Last date of issuance of Tender is 26.08.2020 at 12:00 hrs. The tender will be received upto 27.08.2020, 14:30 hrs and open on same day at 15:00 hrs in presence of opening committee and bidders.

SPECIAL CONDITIONS:-

ELIGIBILITY OF CONTRACTORS

- 1- The Contractor/firm should be registered with Pakistan Engineering Council (PEC), in the field of Mechanical.
- 2- Firm having experience of same job & attach documentary evidence.
- 3- The firm must be registered with FBR, having NTN active tax payer. Also registered with Sindh Revenue Board (SRB).

TENDER CAN BE PURCHASED

- 1) O/O Genco Holding Company Limited, Room No. 196-B, Wapda House, Lahore
- 2) O/O Chief Resident Representative, WAPDA 50-B-1, Block-6, P.E.C.H.S Near P.E.C.H.S Girls College Karachi
- 3) From this Office TPS, Jamshoro during office hours.

EARNEST MONEY (EACH TENDER)

@ 3% of Total Bid Value in Favour of Resident Engineer(M) TPS, Jamshoro in Shape of CDR.

TENDER FEE (EACH TENDER)

Rs. 1000/- only (Non-Refundable) or Rs.1250/- in the shape of Bank Draft (Non Refundable)

PLACE OF OPENING

O/O Chief Engineer/Tech. Director, Main Admn: Building, Thermal Power Station, Jamshoro.


NOTE:

The envelop containing the Tender shall be sealed & addressed to this office should be written following on the top face of the envelop

“ENQUIRY NO” “DUE FOR OPENING ON”

In case Government announces any public holiday or due to unavoidable circumstances, the tender will be opened on next working days.

JPCL reserve the rights to reject all bids or proposals at any time prior to the acceptance of a bid/proposal as per Rule-33 of the PPRA Rules.


 Resident Engineer(Maint.)
 JPCL, Jamshoro

C.c.to:

- 01) Chief Executive Officer, JPCL, Jamshoro.
- 02) Chief Engineer/Tech. Director, JPCL, Jamshoro
- 03) Chief Financial Officer