



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

NO.CEO/RE (O)/CIVIL/ 3300 -05

Dated:- 09/5-/2025.

1. M/s Haji Sawan Lakhan & Co. C/o Nice Tailor Near Marhi Sahab Shahi Bazar Ghotki
2. M/s S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
3. M/s Amaad Construction Company H# A-28, SUECHS Society, Phase-II Jamshoro
4. M/s P.C Chawala & Co. House No. E-191, Gulstan-e-sajjad Qasimabad Hyderabad
5. M/s Paradise Builders Head Off: 19-B-Block G, Johar Town, Lahore

QUOTATION

SUBJECT: **REPAIR & MAINTENANCE ROOF TREATMENT AND PARAPET WALL REPAIRING QUARTER NO. D-242 AND CONSTRUCTION OF DAMAGED BOUNDARY WALL OF QUARTER NO. E-472 AND ONLY OVERHEAD TANK REPAIRING OF QUARTER NO. E-426 AT RESIDENTIAL COLONY AT TPS, JAMSHORO.**

Quotations for the above subject work are hereby invited from your company / firm on percentage rate basis on the following terms and conditions.

SR. NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
01	Removing Cement plaster	Sqm	131.72	45.18	5951.11
02	Cement plaster (1:4) upto 6.00 Meter Height 13mm thick	Sqm	171.59	374.06	64184.96
03	White washing two coats for ceiling .	Sqm	78.24	55.96	4378.31
04	Colour washing 02 coats	Sqm	146.10	46.93	6856.47
05	Distempering two coats.	Sqm	261.64	113.00	29690.90
06	Panting doors and windows any type Two coats.	Sqm	55.72	363.10	20231.93
07	Painting Shases fan light glazed or gauze doors and windows any type two coat	Sqm	16.36	213.15	3487.13
08	Glass strips for dividing the flooring into panel 40mm thick	RM	103.05	181.14	18666.48
09	Topping of cement Concrete (1:2:4) surface finishing & dividing into panels (b) 40mm	Sqm	151.99	667.49	101451.81
10	Roof treatment (cement concrete plain in corner side) Ratio 1:2:4	Cum	1.58	11363.05	17953.62
11	Providing & fixing wardrob shutter as per standard design of WAPDA Residence i/c Almirah hinges. locks. handles & magnetic catcher complete in all respect (R.A)	Sqm	14.41	4196.09	60465.66
12	Dismantling brick wall in cement mortar.	Cum	2.43	1569.30	3813.40
13	Brick work other than building i/c striking of joint upto 3.00 M height in cement mortar 1:5.	Cum	4.34	11717.37	50853.39
14	Damp Proof course with cement, sand and shingle concrete 1:2:4. (40mm thick)	Sqm	2.84	881.12	2502.38
TOTAL RS.					390,487.55
15	Re-used bricks from dismantled work.	Nos	404.00	11.90	4807.00
TOTAL RS.					385,680.00

Add: Contractor Premium _____ % above/below Rs. _____
Total Rs. _____

Note: The rates must be quoted excluding GST/SST

Sr. No	Description	Type	Make / Company
1	Cement (Plaster work)	Ordinary Portland Cement	Lucky, Black bull and DG Khan cement etc.
2	Colour	Distemper	Hypelic, Corona, Diamond & Burger
3	Colour	Weather shield	Hypelic, Corona, Diamond & Burger

SPECIAL CONDITIONS

- 01- The Quotation shall be received on 27-05-2025 at 11:30 in Tender / Quotation box at office of CE/TD and Opened at 12:00 on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

ENQUIRY**DUE FOR OPENING ON**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 30 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 1500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill.
- 14- **Any concrete / cube, brick test or other related test if asked by civil works committee (CWC) will be carried out by the contractor / firm and its expenses will be beared by the firm**


Resident Engineer (O)
(GENCO-I) JPCL, Jamshoro.

Cc.to:

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.