



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

Dated:- 19 / 8 - /2024.

NO.CEO/RE(O)/CIVIL/ 7518-99

1. M/s S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
2. M/s Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
3. M/s P.C Chawala & Co, House No. E-191, Qasimabad Hyderabad Gulstan-e-sajjad, Hyderabad
4. M/s Paradise Builders Head Off: 19-B-Block G, Johar Town, Lahore
5. M/s Amaad Construction Company H# A-28, SUECHS Society, Phase-II Jamshoro

QUOTATION

SUBJECT: **CONSTRUCTION OF 03 NO'S MAIN HOLES ALONG WITH PROVIDING/FIXING SEWERAGE RCC PIPE LINE CONNECT TO EXISTING E-TYPE SEWERAGE MAIN HOLE IN RESIDENTIAL COLONY TPS JAMSHORO.**

Quotation for the above subject work are hereby invited from your company/ firm on percentage rate basis on the following terms and conditions.

SR.No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Excavation in shingle or gravel formation and rock not requiring blasting undressed lead upto 50m (dry)	Cum	98.77	704.95	69627.91
2	Excavation in hard rock requiring blasting and disposal of excavated material (blasted material) up to 30m lead (including dressing and leveling to designed section etc, complete)	Cum	13.76	1251.54	17221.19
3	P/Lowering laying in to trenches and jointing cement concrete reinforced pipeline to correct alignment & grade including cutting of pipes where necessary cost jointing material & testing with internal diameter 300mm.	Rm	47.24	2010.40	94971.29
4	Bricks work ground floor i/c striking of joint cement sand mortar 1:3	Cum	4.84	12728.07	61603.85
5	Cement concrete plain i/c placing compacting finishing and curing complete (i/c screening and washing of stone Aggregate 1:4:8	Cum	0.85	8665.60	7365.76
6	Cement Concrete plain including placing compacting finishing and Curing complete (Including Screening and washing of stone Aggregate) 1:2:4.	Cum	0.56	11363.05	6363.30
7	Reinforced cement concrete work using course sand except the cost of steel reinforcement and irs labour for bending and bending. This rate also includes all kind forms moulds: lifting shuttering, curing, rendering and finshing the exposed surface (including screening and washing of shingle Ratio 1:2:4	Cum	0.85	23643.87	20097.28
8	Supply and Fabrication of intermediate grade deformed reinforcement for RCC in slabs, beams, columns and pile caps, including cutting, bending, laying in position, making joints and fastening i/c cost of binding wire, a 40,000psi (276 Mpa yield) 12mm dia bars	Kg	53.70	250.66	13460.44
9	Cement Plaster (1:4) upto 1 st floor 13mm thick	Sqm	20.07	374.06	7507.38
10	Refilling excavated stuff in trenches in 150mm thick layers including watering, ramming to compaction etc complete	Cum	98.31	341.45	33567.94
11	Flat brick flooring laid in 1:6 cement sand mortar over a bed of 20mm cement mortar 1:6	Sqm	21.61	1064.23	22998.01
TOTAL RS.					354,784.00

Add: Contractor Premium _____ % above/below Rs. _____

Total Rs. _____

Note: The rates must be quoted excluding GST/SST

Sr. No	Description	Type	Make / Company
1	Cement plaster work, court yard, roof topping etc)	Ordinary Portland cement	Lucky, Black bull and D.G khan cement etc
2	Bricks		777,SKB
3	Reinforcement(steel)	60grade	prime suprem ,Agha steel .Amrelli

[Handwritten signature and date]
21/8/24

SPECIAL CONDITIONS

- 01- The Quotation shall be received on 21-08-24 at 11:30 in Tender / Quotation box at office of CE/TD and Opened at 12:02 on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

ENQUIRY**DUE FOR OPENING ON**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 20 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 1500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill.
- 14- **Bricks strength test or other related test if asked by civil works committee (CWC) / civil section will be carried out by the contractor / firm and its expenses will be borne by the firm**


Resident Engineer (O)
(GENCO-I) JPCL, Jamshoro.

Cc.to:

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.