



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

NO.CEO/RE(O)/CIVIL/ 4186-91

Dated:- 02 / 04 /2021.

1. M/S Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
2. M/S P.C Chawala & Co., House No. E-191 Gulstan-e-sajjad, Qasimabad Hyderabad
3. M/S Makkah Madina Engineering, C/O Raja General Store, Hyderabad Bunglow Qasimabad, Hyderabad
4. M/S Sajjad Sarwar & Brothers B-11, Mehran Homes, Citizen Colony, Qasimabad Hyderabad
5. M/S Ghulam Sarwar & Co, B-11 Mehran Homes, Gulistan-E-Sajjad, Qasimabad Hyderabad

QUOTATION

SUBJECT: **SPECIAL REPAIR & MAINTENANCE, REPLACEMENT OF KITCHEN CABINET & PROVIDING & LAYING PCC FLOORING OF COURT YARD OF BUNGALOW NO. C-82 IN RESIDENTIAL COLONY TPS, JAMSHORO.**

Quotations for the above subject work are hereby invited from your company/firm on percentage rate basis on the following terms and conditions.

SR.No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Removing cement plaster.	Sqm	65.06	24.38	1586.16
2	Cement Plaster (1:4) upto 6.00 meter height. 13mm thick	Sqm	65.06	203.67	13250.77
3	White washing two coats	Sqm	116.03	29.73	3449.57
4	Distempering two coats Alpha, Corona,	Sqm	562.28	64.41	36667.32
5	Panting doors and windows any type Two coats Corona, ICI	Sqm	77.19	183.10	14133.49
6	Panting Shases fan light glazed or Gauze doors and windows any typ Two coats. Corona, ICI	Sqm	50.33	107.58	5414.50
7	Glazing with Pans 454 to 512 gm use with putty	Sqm	3.72	732.46	2724.75
8	Colour washing 02 Coats	Sqm	257.99	22.85	5895.07
9	P/Fixing steel tublar frame 1- 1/2" x 1" x 1/16" for ward robe / Almirah i/c cutting bending welding etc. all labour and material as per (R.A).	Rm	11.89	485.20	5769.03
10	Providing & fixing wardrob shutter as per standard design of WAPDA Residence i/c Almirah hinges, locks, handles & magnatic catcher complete in all respect as per drawing. (R.A)	Sqm	3.72	2495.95	9284.93
11	Cement concrete with brick or stone blast 38 to 51mm size in foundation & plinth Ratio 1:4:8	Cum	11.45	3918.10	44862.25
12	Topping of cement concrete 1:2:4 i/c placing compacting and finishing complete 40 mm	Sqm	212.83	365.64	77819.16
13	Glass strips for dividing the floor into panels 40mm	R.M	304.79	80.05	24398.44
TOTAL RS.					2,45,255.00

Add: Contractor Premium _____ % above/below Rs. _____
Total Rs. _____

