



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

NO.CEO/RE(O)/CIVIL/ 5919-93

Dated:- 16/6/2022.

1. M/S Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
2. M/S S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
3. M/S Techno-Pak Construction Co, H. A #-4/09 Mehran University Housing Society District Jamshoro
4. M/S Fayyaz Traders, 19/B Mir Fazal Town Latifabad, Hyderabad
5. M/S Makkah Madina Engineering, C/O Raja General Store, Hyderabad Bunglow Qasimabad, Hyderabad

QUOTATION

SUBJECT: **SPECIAL REPAIR & MAINTENANCE, ROOF TREATMENT, RENOVATION OF TOILET AND FLUSH DOOR OF BUNGLOW NO. B-10 IN RESIDENTIAL COLONY TPS, JAMSHORO.**

Quotations for the above subject work are hereby invited from your company/firm on percentage rate basis on the following terms and conditions.

SR. No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Excavation in trench for water supply pipe line in all kind of soil hard, average or soft upto 1.5 m depth from ground level, including trimming, dressing sides, leveling the bed of trench to correct grade and cutting in pits for joints.	Cum	12.39	334.09	4139.37
2	Dismantling cement concrete plain 1:4:8	Cum	3.72	2030.36	7552.93
3	Providing, Lowering & Laying into Trenches & Jointing cement Concrete Reinforcement Pipe Line to correct alignment & grade i/c cutting of pipes where necessary cost of jointing material & testing with internal diameter				
	a) 100 mm dia	Rm	21.34	108.58	2317.09
	b) 150mm Dia	Rm	42.68	108.58	4634.19
4	Disjointing RCC pipes inside the trench and dismantling and removing the pipes from the trench and stacking them outside.	Rm	42.60	43.07	1834.78
	a) 150 to 300 mm Dia				
5	Re-filling the excavated stuff in trenches in 150 mm thick layers i/c watering, ramming to compaction etc complete	Cum	12.39	341.45	4230.57
6	Cement concrete plain i/c placing, compacting, finishing and curing complete (i/c screening and washing of stone aggregate) without shuttering Ratio:1:4:8	Cum	2.48	8665.60	21490.69
7	Cement concrete plain i/c placing, compacting, finishing and curing complete (i/c screening and washing of stone aggregate) without shuttering Ratio:1:2:4	Cum	1.24	11363.05	14090.18
8	Providing and fixing Flush door leaf as per CDO Standard Drawing	Sqm	11.38	6109.00	69520.42
9	Topping of cement concrete 1:2:4 i/c surface finishing & dividing into pannals b) 40mm thick	Sqm	315.98	667.49	210913.49
10	Glass strip for dividing the flooring into panels b) 40mm wide	Rm	412.8	181.14	74774.59
11	Flooring comprising of glazed tiles 6mm thick laid in white cement mortar 1:2 over 20mm thick cement mortar 1:2 complete a) White	Rm	20.52	3242.80	66542.26
TOTAL RS.					4,82,040.00


Add: Contractor Premium _____ % above/below Rs.
Total Rs. _____

SPECIAL CONDITIONS

- 01- The Quotation shall be received on 28-6-22 at 12:00 in Tender / Quotation box at office of CE/TD and Opened at 12:30 on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

DUE FOR OPENING ON**ENQUIRY**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 25 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill


 Resident Engineer (O)
 (GENCO-I) JPCL, Jamshoro.

Cc.to:

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.