



# JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE  
CHIEF EXECUTIVE OFFICER  
JPCL JAMSHORO.

NO.CEO/RE (O)/CIVIL/ 1373-78

Dated:- 14/2-/2023.

1. M/S Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
2. M/S P.C Chawala & Co, House No. E-191 Gulstan-e-sajjad, Qasimabad Hyderabad
3. M/S S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
4. M/S Techno-Pak Construction Co, H. A #-4/09 Mehran University Housing Society District Jamshoro
5. M/S Fayyaz Traders, 19/B Mir Fazal Town Latifabad, Hyderabad
6. M/S The Ellahi & Sons Engineering Works near Shell Petroleum Sehven Road Jamshoro

## QUOTATION

SUBJECT: **REPAIR ROOF TREATMENT ON LEAKAGE AREAS COLOURING PAINTING & MAINTENANCE OF BUNGALOW NO. B-17 IN RESIDENTIAL COLONY AT TPS, JAMSHORO.**

Quotations for the above subject work are hereby invited from your company / firm on percentage rate basis on the following terms and conditions.

SR. NO.	DESCRIPTON	UNIT	QTY	RATE	AMOUNT
1	White washing two coats.	Sqm	219.74	55.96	12296.65
2	Distempering two coats.	Sqm	776.97	113.00	87797.61
3	Panting doors and windows any type Two coats.	Sqm	71.65	363.10	26016.12
4	Panting Shases fan light glazed or Gauze doors and windows any type Two coats.	Sqm	48.37	213.15	10310.07
5	Colour washing Two coats.	Sqm	470.49	46.93	22080.10
6	Glazing pans 454 to 512 gms use with putty	Sqm	7.81	1360.42	10624.88
7	Topping of cement Concrete (1:2:4) surface finishing & dividing into panels (b) 40mm	Sqm	115.61	667.49	77168.51
8	Glass strips for dividing the flooring into panel 40mm wide (Roof)	Rm	184.39	181.14	33400.40
9	Removing Cement plaster (1:4) upto 1 <sup>st</sup> floor height (b) 13mm @ C/W ground floor 3m height	Rm	62.68	45.18	2831.88
10	Cement Plaster (1:4) upto 1st floor height: (b) 13mm and 3m height at ground floor	Sqm	62.68	374.06	23446.08
11	Expanded metal 13mm to 20mm mesh 16 gauge fixed to chowkat with 25mm teak wood moulding/strips and screws for window	Sqm	9.37	5349.86	50128.19
12 (a)	Dismantling cement concrete street manhole to manhole chowked sewerage line 1:2:4	Cum	0.53	4061.70	2152.70
(b)	Excavation in shingle gravel formation & rock not recovering, blasting undersers laid upto 50 m chowked sewerage pipe line	Cum	2.66	334.09	888.67
13	Cement concrete Ration 1:2:4	Cum	1.26	11363.05	14317.44
14	C.I soil pipes with lead chowked joints for diameter replace chowked sewerage pipe line 100mm	M.R	7.62	3423.87	26089.89
15	Replace cabinet eaten by termite of paintry providing & fixing laminated board for wardrobe shutter complete in all respect	Sqm	18.22	4196.09	76452.76
16	Providing fixing quality mortice lock	No	8.00	1192.91	9543.28
<b>TOTAL RS.</b>					<b>4,85,546.00</b>

Add: Contractor Premium \_\_\_\_\_ % above/below Rs. \_\_\_\_\_  
Total Rs. \_\_\_\_\_

*[Signature]*  
14.02.2023




**SPECIAL CONDITIONS**

- 01- The Quotation shall be received on 28-02-2023 at 12-00 PM in Tender / Quotation box at office of CE/TD and Opened at 12:30 PM on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

**ENQUIRY****DUE FOR OPENING ON**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 25 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 1500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill

 21.4.2.2023  
Resident Engineer (O)  
(GENCO-I) JPCL, Jamshoro.

**Cc.to:**

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.