



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

NO.CEO/RE(O)/CIVIL/ 9439-43

Dated:- 13 / 09 /2023.

1. M/s Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
2. M/s S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
3. M/s Techno-Pak Construction Co, H. A #-4/09 Mehran University Housing Society District Jamshoro
4. M/S Fayyaz Traders, 19/B Mir Fazal Town Latifabad, Hyderabad
5. M/s The Ellahi & Sons Engineering Works Near Shell Petroleum Sehven Road JamshoroCamp at Qtr: E-468 JPCL Colony Jamshoro

QUOTATION

SUBJECT: RENOVATION OF BUNGALOW NO. C-39 IN RESIDENTIAL COLONY TPS, JAMSHORO.

Quotations for the above subject work are hereby invited from your company/ firm on percentage rate basis on the following terms and conditions.

SR.No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Removing cement plaster	Sqm	38.37	45.18	1733.55
2	Cement Plaster (1:4) upto 6.00 meter height (b) 13mm thick.	Sqm	76.74	374.06	28705.36
3	Dismantling cement concrete plain 1:2:4	Cum	1.96	4061.77	7961.07
4	Cement concrete 1:4:8	Cum	0.98	7027.26	6886.71
5	Cement concrete 1:2:4	Cum	0.98	11363.05	11135.79
6	Excavation of trenches for water supply pipe lines in all kinds of soil, hard, average or soft upto 1.5 m depth from ground level, including trimming, dressing side, leveling the bed of trench	Cum	8.92	334.09	2980.08
7	Providing lowering & laying into trenches & jointing cement concrete Reinforcement pipe line to correct alignment & grade i/c cutting of pipes where necessary cost of jointing material & testing wth internal diameter (b) 150mm dia	RM	12.80	1167.80	14947.84
8	White Washing 02 coats for ceiling	Sqm	116.03	55.96	6493.04
9	Distempering two coats	Sqm	511.93	113.00	57848.09
10	Panting doors and windows any type Two coats.	Sqm	77.19	363.10	28027.69
11	Panting Shases fan light glazed or Gauze doors and windows any typ Two coats.	Sqm	16.78	213.15	3576.66
12	Colour washing 02 coats	Sqm	59.57	46.93	2795.62
13	Topping of cement concrete 1:2:4 i/c surface finishing and dividing into panels 40mm thick	Sqm	156.60	667.49	104528.93
14	Glass strips for dividing the floor into panels 40mm thick	Rm	140.51	181.14	25451.98
15	P/Fixing steel tublar frame 1"x2"x1/16" and 1/2"x1"x1/16" for ward robe / Almirah i/c cutting bending welding etc. all labour and material as per drawing. As a approved by the engineer incharge .	Rm	6.91	485.20	3352.73
16	P/Fixing laminated board for Ward-Robe shutter complete in all respect	Sqm	11.43	4196.09	47961.31
17	Providing fixing flush door leaf as per CDO standard drawing	Sqm	6.18	6109.00	37753.62
18	Providing & fixing approved quality mortice lock	No	4.00	1192.19	4768.76
19	Flooring comprising of mosaic marble chips cement tiles of approved shad laid in cement mortar 1:2 including finishing complete	Cum	2.79	1293.06	3607.64
20	Dismantling cement concrete plain Ration 1:2:4	Cum	0.17	4061.77	690.50
21	Supplying and fabrication of intermediate grade. Deformed Reinforcement for RCC in slab 3/8" dia bar 6" c/c	Kg	16.47	250.66	4128.37
22	Reinforced cement concrete work using course sand i/c all labour and material expect steel reinforcement i/c screening washing of shingle	Cum	0.17	23643.87	4019.46
TOTAL RS.					409,355.00

Add: Contractor Premium _____ % above/below Rs. _____

Total Rs. _____

Note: The Quoted Rates are excluding GST/SST

[Signature]
13/9/23

SPECIAL CONDITIONS

- 01- The Quotation shall be received on 26-9-2023 at 12:00 in Tender / Quotation box at office of CE/TD and Opened at 12:30 on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

ENQUIRY**DUE FOR OPENING ON**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 20 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 1500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill


Resident Engineer (O)
(GENCO-I) JPCL, Jamshoro.

Cc.to:

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.