



# JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE  
CHIEF EXECUTIVE OFFICER  
JPCL JAMSHORO.

NO.CEO/RE (O)/CIVIL/ 8579-83

Dated:- 16 / 09 / 2022.

1. M/S Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
2. M/S Fayyaz Traders, 19/B Mir Fazal Town Latifabad, Hyderabad
3. M/S S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
4. M/S Techno-Pak Construction Co, H. A #-4/09 Mehran University Housing Society District Jamshoro
5. M/S Makkah Madina Engineering, C/O Raja General Store, Hyderabad Bungalow Qasimabad, Hyderabad

## QUOTATION

SUBJECT: **CONSTRUCTION OF DAMAGED BOUNDARY WALL OF BUNGALOW NO. B-03 & B-07 BACK SIDE ATTACHED BOUNDARY WALL AT RESIDENTIAL COLONY AT TPS, JAMSHORO.**

Quotations for the above subject work are hereby invited from your company / firm on percentage rate basis on the following terms and conditions.

| SR. NO.          | DESCRIPTON   | UNIT | QTY     | RATE     | AMOUNT             |
|------------------|--|------|---------|----------|--------------------|
| 1                | Dismantling of brick work in cement concrete   | Cum  | 17.36   | 1569.30  | 27243.04           |
| 2                | Dismantling cement concrete 1:4:8  | Cum  | 4.62    | 2030.36  | 9380.26            |
| 3                | Cement Concrete lain i/c placing compacting finishing and curing complete i/c screaming and washing of stone aggregate) without shuttering Ratio 1:4:8                       | Cum  | 4.62    | 8665.60  | 40034.61           |
| 4                | Brick work other than building i/c striking of joints up to 3 Mtrs height in cement sand mortar (1:5)  | Cum  | 29.19   | 11717.37 | 342030.03          |
| 5                | Cement plaster (1:4) upto 1 <sup>st</sup> floor height 13mm thick  | Sqm  | 231.72  | 374.06   | 86677.18           |
| 6                | Damp proof course with cement sand and shingle concrete 1:2:4 i/c 02 coats of asphaltic mixture (a) 40mm thick   | Sqm  | 13.01   | 881.12   | 11463.37           |
| 7                | Cement pointing struck joints on walls in Ratio:1:2  | Rm   | 27.88   | 411.08   | 11461.18           |
| 8                | Scraping or cleaning bricks dismantling from masonry   | Nos  | 4207    | 1.73     | 7695.04            |
| 9                | Dismantling fencing all type of wire fencing i/c rolling wire into bundles & collecting material   | Rm   | 50      | 30.47    | 1523.50            |
| 10               | Fixing & grouting angle iron post only labour providing by department 1:2:4.   | Each | 5       | 200.40   | 1002.10            |
| 11               | Providing and fixing G.I 1.5m length 50 x 50 x 6mm angle iron post for barbid wire fencing around switch yard duly fixed in position (Dwg No. PDW/TB-126) without angle iron | Each | 5       | 608.73   | 3043.65            |
| 12               | Providing and fixing 4 Rows barbid wire (only Labour)  | Rm   | 12.50   | 189.05   | 2363.12            |
| <b>TOTAL RS.</b> |  |      |         |          | <b>5,43,917.00</b> |
| 13               | Re-used brick from dismantling work  | Nos  | 4207.10 | 11.90    | 50063.30           |
| <b>TOTAL RS.</b> |  |      |         |          | <b>4,93,853.00</b> |


Add: Contractor Premium \_\_\_\_\_% above/below Rs. \_\_\_\_\_  
Total Rs. \_\_\_\_\_

**SPECIAL CONDITIONS**

- 01- The Quotation shall be received on 23-8-22 at 11:00 in Tender / Quotation box at office of CE/TD and Opened at 11:30 on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

**DUE FOR OPENING ON****ENQUIRY**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 20 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 1500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill

  
Resident Engineer (O)  
(GENCO-I) JPCL, Jamshoro.

**Cc.to:**

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.