



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

NO.CEO/RE (O)/CIVIL/6205-09

Dated:- 03/7-/2024.

1. M/s Haji Sawan Lakhan & Co, C/o Nice Tailor Near Marhi Sahab Shahi Bazar Ghotki
2. M/s S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
3. M/s Amaad Construction Company H# A-28, SUECHS Society, Phase-II Jamshoro
4. M/s P.C Chawala & Co, House No. E-191, Gulstan-e-sajjad Qasimabad Hyderabad
5. M/s Paradise Builders Head Off: 19-B-Block G, Johar Town, Lahore

QUOTATION

SUBJECT: **REPAIR & MAINTENANCE OF 02 NOS QUARTER NO. D-182 & D-209 AND ONLY ROOF TOPPING, PARAPET WALL REPAIRING OF 01 NO QUARTER OF D-182 AT RESIDENTIAL COLONY AT TPS, JAMSHORO.**

Quotations for the above subject work are hereby invited from your company / firm on percentage rate basis on the following terms and conditions.

SR. NO.	DESCRIPTON	UNIT	QTY	RATE	AMOUNT
1	Removing Cement plaster	Sqm	51.93	45.18	2346.19
2	Cement plaster (1:4) upto 6.00 Meter Height 13mm thick	Sqm	51.93	374.06	20651.85
3	White washing two coats for ceiling .	Sqm	167.65	55.96	9381.69
4	Colour washing Two coats.	Sqm	292.19	46.93	13712.47
5	Distempering two coats.	Sqm	523.22	113.48	59375.00
6	Panting doors and windows any type Two coats.	Sqm	111.42	363.10	40456.60
7	Panting Shases fan light glazed or Gauze doors and windows any type Two coats.	Sqm	32.70	213.15	6970.00
8	Topping of cement Concrete (1:2:4) surface finishing & dividing into panels (b) 40mm	Sqm	175.00	667.49	116810.75
9	Glass strips for dividing the flooring into panel 40mm thick	Rm	249.92	181.14	45270.50
10	Cement concrete plain in corner side (Gola) Ratio: 1:2:4	Cum	0.48	11363.05	5454.26
11	Providing & fixing steel tublar frame 1" x 2" x 1/16" & 1/2" x 1" x 1/16" for wardrob Almirah i/c cutting, bending, welding etc or labour & material (R.A).	Rm	11.88	485.20	5764.17
12	Providing & fixing wardrob shutter as per standard design of WAPDA Residence i/c Almirah hinges, locks, handles & magnatic catcher complete in all respect	Sqm	3.71	4196.09	15567.17
13	Dismantling brick wall in cement mortar	Cum	0.54	1569.30	847.42
14	Brick work other than building i/c striking of joint upto 3.00 m height in cement sand mortar 1:5	Cum	0.54	11717.37	6327.38
TOTAL RS.					348935.45
15	Re-used bricks from dismantled work	Nos	103.41	11.90	1225.70
TOTAL RS.					347,710.00

Add: Contractor Premium _____ % above/below Rs. _____
Total Rs. _____

Note: The Quoted Rates are excluding GST/SST

SPECIAL CONDITIONS

- 01- The Quotation shall be received on 11-07-2024 at 11:30AM in Tender / Quotation box at office of CE/TD and Opened at 12:00PM on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

ENQUIRY**DUE FOR OPENING ON**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is **30** Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 1500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill.
- 14- **Any concrete / cube test or other related test if asked by civil works committee (CWC) will be carriedout by the contractor / firm and its expenses will be beared by the firm**


Resident Engineer (O)
(GENCO-I) JPCL, Jamshoro.

Cc.to:

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.