

# JAMSHORO POWER COMPANY LIMITED

A Subsidiary Company of Water & Power Development Authority

Phone : 9213706  
Fax : 9213707

OFFICE OF THE  
CHIEF EXECUTIVE OFFICER  
JPCL (GENCO-I)  
JAMSHORO

No.CEO/RE(O)/CIVIL/ 3600-04

Dated. 29-4-2022.

- 1- M/s. Rashid Engineering Company, C-22, Al-Rehman Appartment, Old Hala Naka, Hyderabad.
- 2- M/s. Bismillah Engineering Works, 315, Area 48/H, Haq Baho Town, Korangi No.1 Karachi
- 3- M/s. P.C Chawla & Co, House No. E-191 Gulistan-e-Sajjad, Qasimabad, Hyderabad
- 4- M/s. SRK Engineering Company, 83, Isra Village, Old Hala Naka Road, Hyderabad
- 5- M/s. Fayyaz Traders, 196/B, Mir Fazal Town, Latifabad Unit No.9, Hyderabad.

## QUOTATION

Subject:- **SPECIAL RENOVATION OF 03 NOS. TOILET, REPLACEMENT OF KITCHEN CABNETS AND 01 NO. ALMIRAH, SETTLED FLOOR OF ROOMS AND REPLACEMENT OF SEWERAGE LINE OF BUNGLOW NO. B-20 IN RESIDENTIAL COLONY TPS, JAMSHORO.**

Quotation for the above subject work are hereby invited from your company / firm on percentage rate basis on the following terms and conditions.

SR. NO.	DESCRIPTION	UNIT	Qty:	Est. Rate Rs.	Amount Rs.
1-	Excavation shingle or gravel formation and rock not requiring blasting undressed lead upto 50 m a) dry (WCSR-2013 P-2-1/4 (a))	Cum	21.78	380.40	8285.11
2-	Cement concrete plain i/c placing, compacting, finishing and cujring complete (i/c screening and washing of stone aggregate) without shuttering Ratio: 1:2:4 (WCSR-2013 P-5-1/2 (b))	Cum	4.36	6343.62	27658.18
3-	Providing and laying RCC Pipe (WCSR-2013 P-13 P-13-8/23 (a))				
a)	100mm dia	RM	19.51	464.36	9059.66
b)	150mm dia	RM	27.43	661.70	18150.43
4-	Providing / fixing steel tublar frame 1" x 2" x 16" & 1/2" x 1" x 16" for ward robe /Almirah / cutting bending, welding etc all labour and material as per drawing (R.A)	RM	48.69	485.12	23620.49
5-	Providing / fixing Wardrobe shutter as standard design of WAPDA Residences i/c Almirah hinges locks Handles and magnetic catchers etc complete in all respect as per Drawing (R.A)	Sqm	11.62	2495.95	29002.94
6-	Flooring comprising of glaze tiles 6mm thick laid in white cement mortar 1:2 over 20mm thick cement mortar Ratio 1:2 complete a) White (WCSR-2013 P-9-3/16 (a))	Sqm	69.69	1210.58	84365.32
7-	Deodar wood wrought Joint in work in doors and windows etc fixed in posiont i/c chowkats, holefast, hinges, iron tunner bolt chocks handles and cords with hooks 40mm thick (WCSR-2013 P-11-2/6 (c))	Sqm.	9.11	9910.65	90286.02
8	C.I Soil Pipe with lead (WCSR-2013 P-13-23/112)				
a)	50mm dia	RM	12.00	1394.72	16736.64
b)	100mm dia	RM	15.00	1945.17	29177.55
9-	Floor top 100mm x 50mm (WCSR-2013 P-13-23/108 (a))	No.	03	438.74	1316.22
10-	Chromium plated or oxidized swanneck cocks 13mm dia two way (WCSR-2013 P-13-23/102(b))	RM	03	1179.91	3539.73
11-	Chromium plated shower 13mm complete with CP Arm 02 Nos. CP Stop Cocks 1 No. CP Bib Cock 01 Nos. CP Shower (WCSR-2013 P-13-22/97)	No.	03	3139.78	9419.34



SR. NO.	DESCRIPTION	UNIT	Qty:	Est. Rate Rs.	Amount Rs.
12-	CP Tee Stop Cocks 13mm dia (WCSR-2013 P-13-21/94 (a))	No.	03	449.84	1349.52
13-	Connection 13mm dia PVC (WCSR-2013 P-13-21/92 (a))	No.	03	160.57	481.71
14-	Waste pipe for Sink PVC (WCSR-2013 P-13-21/89 (a))	No.	06	147.05	882.30
15-	PVC flushing bend 32mm (WCSR-2013 P-13-21/87 (a))	No.	03	73.58	220.74
16-	CP Waste Coupling (WCSR-2013 P-13-20/84 (a))	No.	03	284.80	854.40
17-	CP Bib Tap (WCSR-2013 P-13-20/82)	No.	24	468.46	11243.04
18	Looking glass 550mm x 400mm (WCSR-2013 P-13-20/77 (a))	No.	03	689.34	2068.02
19	White glazed earthen ware bidet with all hardware fittings complete of supreme quality (WCSR-2013 P-13-19/72)	No.	03	5902.29	17706.87
20-	White glazed earthen ware wash and basin domestic of supreme quality 65 cm (WCSR-2013 P-13-18/64)	No.	03	1249.04	3747.12
21-	White glazed earthen ware pendastal for wash & basin (WCSR-2013 P-13-19/65)	No.	03	1179.16	3537.48
22-	White glazed earthen ware water closet squatting type domestic (WCSR-2013 P-13-18/62)	No.	03	1615.36	4846.08
23-	Low level flushing Cistern 13.50 Ltrs capacity Plastic (WCSR-2013 P-13-19/70 (b))	No.	03	1764.83	5294.49
24-	Brick work other than building i/c striking of joints upto 3 Mtr. Height cement mortar Ratio 1:5 (WCSR-2013 P-6-1/4)	Cum	2.91	6934.73	20180.06
25-	Cement plaster (1:4) upto 1 <sup>st</sup> Floor height 13mm (WCSR-2013 P-10-1/5(b))	Sqm.	4.26	203.67	867.63
<b>Total Rs.</b>					<b>423897.09</b>

Add: Contractor Premium \_\_\_\_\_ % above/Below Rs. \_\_\_\_\_

Total Rs. \_\_\_\_\_

### **SPECIAL CONDITIONS**

- 01- The Quotation shall be received on 13-5-22 at 11:00 in Tender /Quotation box at office of CE/TD and Opened at 11:30 on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with over writing / cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

### **ENQUIRY**

### **DUE FOR OPENING ON**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.

- 06- The payment will only be made for the work carried out according to the standard applicable specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove /replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bid's or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day.
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached.
- 10- Time of completion is 30 days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 500/- Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill.

  
29/4/22  
RESIDENT ENGINEER(O)  
TPS, JAMSHORO

C.c.to:

- 1) Chief Executive Officer, JPCL, Jamshoro
- 2) Chief Financial Officer, JPCL, Jamshoro.
- 3) Executive Engineer (Civil), TPS, Jamshoro.
- 4) Notice Board.