



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

NO.CEO/RE (O)/CIVIL/ 9092-96

Dated:- 15/3-/2023.

1. M/s Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
2. M/s Kifayat Baloch C-137 Gulistan e Fatima Phase-II Near Mubarak Society Hyderabad
3. M/s Fayyaz Traders, 19/B Mir Fazal Town Latifabad, Hyderabad
4. M/s S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
5. M/s Techno-Pak Construction Co, H. A #-4/09 Mehran University Housing Society District Jamshoro

QUOTATION

SUBJECT: REPLACEMENT OF RCC SEWERAGE LINE FOR D-215 TO 217, E-46 TO 81, E-107 TO 109, E-152 TO 154, E-226 TO 227, E-262 TO E-263 & E-206 TO E-243 IN RESIDENTIAL COLONY TPS, JAMSHORO.


Quotations for the above subject work are hereby invited from your company/ firm on percentage rate basis on the following terms and conditions.

SR.No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Dismantling brick or concrete flooring	Sqm	153.75	168.33	25880.73
2	Excavation for water supply pipe line in all kinds of soil hard average or soft upto 1.5 m depth from ground level, including trimming, dressing sides, leveling the bed of trench to correct grade and cutting in pits for joints.	Cum	82.10	816.32	67019.87
3	P/Lowering & laying in to trenches jointing cement concrete reinforced pipeline to correct alignment & grade i/c cutting of pipes where necessary cost of jointing material & testing with 250mm internal diameter 225mm dia	Rm	102.60	1579.96	162103.89
4	Refilling excavated stuff in trenches in 150mm thick layers i/c watering, ramming to compaction etc complete	Cum	82.10	341.45	28033.04
5	Flat brick flooring laid in 1:6 cement sand mortar over a bed of 20mm cement mortar 1:6	Sqm	153.75	1064.23	163625.36
6	Scraping or cleaning bricks dismantled from masonry	No	1737.06	1.73	3005.11
7	Carriage of waste material upto 2 KM	Cum	4.61	241.83	1114.83
TOTAL RS.					450,782.83
8	Cost of re used bricks (standred size)	Nos 0%	1737.06	11900.00	20671.01
TOTAL RS.					430,111.00

Add: Contractor Premium _____ % above/below Rs. _____

Total Rs. _____

Note: The Quoted Rates are excluding GST/SST



15/3/2023

SPECIAL CONDITIONS

- 01- The Quotation shall be received on 29-03-2023 at 12:00 PM in Tender / Quotation box at office of CE/TD and Opened at 12:30 PM on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

ENQUIRY**DUE FOR OPENING ON**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 25 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 1500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill

 215/3/2023
Resident Engineer (O)
(GENCO-I) JPCL, Jamshoro.

Cc.to:

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.