



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

Dated:- 22/11/2023.

NO.CEO/RE (O)/CIVIL/ 11082-86

1. M/s Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
2. M/s P.C Chawala & Co, House No. E-191 Gulstan-e-sajjad, Qasimabad Hyderabad
3. M/s S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
4. M/s Techno-Pak Construction Co, H. A #-4/09 Mehran University Housing Society District Jamshoro
5. M/s Fyyaz Traders, 19/B Mir Fazal Town Latifabad, Hyderabad

QUOTATION

SUBJECT: **REHABILITATION OF BATH ROOMS OF BUNGALOW NO. B-17 & RECONSTRUCTION OF TILTED BOUNDARY WALL OF BUNGALOW NO. B-14 IN RESIDENTIAL COLONY AT TPS, JAMSHORO.**

Quotations for the above subject work are hereby invited from your company / firm on percentage rate basis on the following terms and conditions.

SR. NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Removing Cement plaster	Sqm	19.97	45.18	902.39
2	Cement Plaster (1:4) upto 6.00 meter height: (b) 13mm	Sqm	144.51	374.06	54054.17
3	Dismantling cement concrete	Cum	0.84	1015.18	852.75
4	Excavation or trenches for water supply pipe lines in all kinds of soil, hard, average or soft upto 1.5 m depth from ground level, including trimming, dressing sides, leveling the bed of trench	Cum	3.40	334.09	1135.90
5	Providing Lowering & laying in to trenches and joint cement concrete reinforced pipeline to correct alignment & grade i/c curbing of pipes where necessary cost of jointing material & testing with internal diameter a (100 mm) dia	Rm	9.14	821.37	7507.32
6	Cement concrete plain 1:2:4	Cum	0.56	4061.77	2274.59
7	Dismantling glazed of encaustic tiles etc.	Sqm	20.80	309.10	6429.28
8	Flooring Comprising of glazed tiles 6mm thick laid in white cement mortar 1:2 over 20mm thick cement mortar 1:2 complete (a) White	Sqm	20.80	3242.80	67450.24
9	CP Piller Cock	No	1	826.39	826.39
10	Chromium plated shower 13mm complete with CP arm, 02 Nos. CP stop cocks 01 No. CP bib Cocks ann 01 No Shower	No	3	5226.55	15679.65
11	White glazed earthen ware water closet squatting type domestic Indian pattern of best quality	No	1	4895.25	4895.25
12	Dismantling brick work cement mortar	Cum	8.17	1569.30	12821.18
13	Brick work other than building i/c striking of joints upto 3.0m height on Cement sand mortar. Ratio: 1:5	Cum	8.17	12057.09	98506.42
14	CP tee stop cocks 13mm dia	No	1	787.19	787.19
15	Connection 13mm dia (a) PVC	No	1	306.88	306.88
16	Waste pipe for sink PVC	No	1	263.93	263.93
17	PVC flushing bend 32mm dia	No	2	173.34	346.68
18	PVC flushing bend 32mm dia	No	1	491.44	491.44
19	CP waste coupling 32mm dia	No	2	796.90	1593.80
20	CP Bib Tap	No	2	3156.34	6312.68
21	Low Level flushing cistern 13.5 liter capacity best quality (b) plastic	No			
22	Providing fixing C.I pipe	Rm	3.66	1929.00	7055.17
	75 mm	Rm	1.52	2454.00	3730.08
	100 mm	Sqm	4.46	8043.59	35874.41
23	White marble flooring fine dressed on the surface without winding set in cement mortar 1:2 laid over 20mm thick cement mortar 1:2 i/c rubbline & polishing 9.7 (a) 20mm	Cum	3.40	341.45	1160.41
24	Re-filling of excavated stuff in 150mm thick layers i/c watering, ramming to compaction etc complete	Cum	3.40	341.45	1160.41
25	Providing / Fixing Flush door leaf as per CDO standard drawing	Sqm	16.26	6109.00	99332.34
26	Painting Doors and windows new surface type three coat i/c premier coat	Sqm	32.53	636.84	20716.40
27	Colour washing 02 coat (Lime) (b) two coat over & i/c cost priming coat	Sqm	124.53	46.93	5844.19
				TOTAL RS.	457,151.00
				Nos	1159.83
					11.90
				TOTAL RS.	443,339.00
27	Re-used brick	Nos	1159.83	11.90	13811.97

Add: Contractor Premium _____ % above/below Rs. _____
Total Rs. _____

Note: The Quoted Rates are excluding GST/SST


22/11/23

SPECIAL CONDITIONS

- 01- The Quotation shall be received on 4-12-2023 at 14:00 in Tender / Quotation box at office of CE/TD and Opened at 14:30 on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

DUE FOR OPENING ON**ENQUIRY**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 25 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 1500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill


 Resident Engineer (O)
 (GENCO-I) JPCL, Jamshoro.

Cc.to:

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.