Phone Fax.

9213706 9213707

OFFICE OF THE CHIEF EXECUTIVE OFFICER JPCL (GENCO-I) **JAMSHORO** 

No.CEOJ/RE(M)/QT-149/22/ME(T)/ 3 /50 - 55

Dated. 18-4-2022.

M/s. Rashid Engineering Company, C-22, Al-Rehman Appartment, Old Hala Naka, Hyderabad. M/s. Bismillah Engineering Works, 315, Area 48/H, Haq Baho Town, Korangi No.1 Karachi M/s. Hammad Engineering Works, Plot Number, D-66, Unit No.8, Latifabad, Hyderabad M/s. SRK Engineering Company, 83, Isra Village, Old Hala Naka Road, Hyderabad M/s. Fayyaz Traders, 196/B, Mir Fazal Town, Latifabad Unit No.9, Hyderabad.

## QUOTATION

Subject:-

QUOTATION FOR THE WORK OF EXCAVATION & RE-FILING DISMENTALING, REPAIRING, FABRICATION, ERRECTION, BENDING, MAKING OF MS PIPE LINE 1400 MM DIA FOR DAMAGE PORTION OF UNDER GROUND CW PUMPS RETURN LINE NEAR CONDENSER AT TURBINE HALL UNIT NO.2 TPS JAMSHORO(QT-149/22/ME(T)

Quotation on over all bid price basis for the subjected work as detailed below are hereby invited from your firm on the terms and condition detailed below:

| DESCRIPTION   | UNIT   | Qty:   | Est:<br>Rate<br>Rs.  | Amount<br>Rs.  |
|---|--|--|--|--|
| Excavation single or gravel formation and rock not requiring blasting undressed lead up to 50M dry $L = 11.5 \times W = 5.6 \times D = 2.5 = 161Sqm$ (WSCR-2013, Section-2, Pg-2-1 Item:4(a))   | Sqm  | 158.12   |  |  |
| Dewatering and dismantling of existing eroded portion, fabrication, and bending of MS pipes 1400mm & MS pipe dia 2200mm installation of MS Bend & MS pipe over lap inside the existing damaged portion 1400/200mm of the CW pump return line of unit No.2, job includes dewatering, cleaning, dismantling, erecting, making of bend & pipe, cutting, making window on pipe for working inside pipe, grinding and welding complete in all respect. | Job  | 01   |  |  |
| Refilling the excavated stuff single or gravel formation and rock not requiring blasting undressed lead upto 50M dry. $L=11.5 \times W=5.6 \times D=2.5=161 Sqm$ (WSCR-2013, Section-2, Pg-2-3 Item:13)   | Sqm  | 158.12   | M  |  |
| owest Bid shall be evaluated on overall total bid price.  |  |  | .  |  |
|   | Excavation single or gravel formation and rock not requiring blasting undressed lead up to 50M dry $L=11.5 \times W=5.6 \times D=2.5=161 Sqm$ (WSCR-2013, Section-2, Pg-2-1 Item:4(a))  Dewatering and dismantling of existing eroded portion, fabrication, and bending of MS pipes 1400mm & MS pipe dia 2200mm installation of MS Bend & MS pipe over lap inside the existing damaged portion 1400/200mm of the CW pump return line of unit No.2, job includes dewatering, cleaning, dismantling, erecting, making of bend & pipe, cutting, making window on pipe for working inside pipe, grinding and welding complete in all respect.  Refilling the excavated stuff single or gravel formation and rock not requiring blasting undressed lead upto 50M dry. $L=11.5 \times W=5.6 \times D=2.5=161 Sqm$ (WSCR-2013, Section-2, Pg-2-3 Item:13) | Excavation single or gravel formation and rock not requiring blasting undressed lead up to 50M dry $L=11.5 \times W=5.6 \times D=2.5=161 Sqm$ (WSCR-2013, Section-2, Pg-2-1 Item:4(a))  Dewatering and dismantling of existing eroded portion, fabrication, and bending of MS pipes 1400mm & MS pipe dia 2200mm installation of MS Bend & MS pipe over lap inside the existing damaged portion 1400/200mm of the CW pump return line of unit No.2, job includes dewatering, cleaning, dismantling, erecting, making of bend & pipe, cutting, making window on pipe for working inside pipe, grinding and welding complete in all respect.  Refilling the excavated stuff single or gravel formation and rock not requiring blasting undressed lead upto 50M dry. $L=11.5 \times W=5.6 \times D=2.5=161 Sqm$ (WSCR-2013, Section-2, Pg-2-3 Item:13) | Excavation single or gravel formation and rock not requiring blasting undressed lead up to 50M dry $L=11.5 \times W=5.6 \times D=2.5=161Sqm$ (WSCR-2013, Section-2, Pg-2-1 Item:4(a))  Dewatering and dismantling of existing eroded portion, fabrication, and bending of MS pipes 1400mm & MS pipe dia 2200mm installation of MS Bend & MS pipe over lap inside the existing damaged portion 1400/200mm of the CW pump return line of unit No.2, job includes dewatering, cleaning, dismantling, erecting, making of bend & pipe, cutting, making window on pipe for working inside pipe, grinding and welding complete in all respect.  Refilling the excavated stuff single or gravel formation and rock not requiring blasting undressed lead upto 50M dry. $L=11.5 \times W=5.6 \times D=2.5=161Sqm$ (WSCR-2013, Section-2, Pg-2-3 Item:13)  owest Bid shall be evaluated on overall total bid price.  Add 13 | Excavation single or gravel formation and rock not requiring blasting undressed lead up to 50M dry $L=11.5 \times W=5.6 \times D=2.5=161Sqm$ (WSCR-2013, Section-2, Pg-2-1 Item:4(a))  Dewatering and dismantling of existing eroded portion, fabrication, and bending of MS pipes 1400mm & MS pipe dia 2200mm installation of MS Bend & MS pipe over lap inside the existing damaged portion 1400/200mm of the CW pump return line of unit No.2, job includes dewatering, cleaning, dismantling, erecting, making of bend & pipe, cutting, making window on pipe for working inside pipe, grinding and welding complete in all respect.  Refilling the excavated stuff single or gravel formation and rock not requiring blasting undressed lead upto 50M dry. $L=11.5 \times W=5.6 \times D=2.5=161Sqm$ (WSCR-2013, Section-2, Pg-2-3 Item:13)  Total Rs. Add 13% SRB Rs |

## SPECIAL CONDITIONS:-

The Quotation shall be received at 11:30 Hrs on 26.04.2022 and opened on same day at 12:00 Hrs at the o/o Resident Engineer(M), Main Admn. Building, Thermal Power Station, Jamshoro in presence of the bidder, who care to be present.

The quotation may be deposited in the tender box kept for the purpose in the office of the Resident Engineer(M) Main Admn. Building, Thermal Power Station, Jamshoro before due date and time for opening as above. The quotations received late will not be considered. The quotations received with over writing/cutting and having doubtful figures will be rejected.

The envelope containing the quotation shall be sealed & addressed to this office should be written following on the top face of the envelop.

"ENQUIRY NO"

"DUE FOR OPENING ON"

The work shall be carried out according to the standard design and specification and instruction of the Engineer Incharge.

The payment will only be made for the work carried out according to the standard applicable specifications and satisfaction of the Engineer Incharge. The under specification work & material shall be rejected & will have to be removed/replaced by contractor at his own risk & cost. In case Government announces any public holiday or due to unavoidable circumstances, the tender will be opened on next working days. JPCL reserve the rights to reject all bids or proposals at any time prior to the acceptance of a bid/proposal as per Rule-33 of the PPRA. All the consumable material in electrode, gases, grinding disk, T&P, Labour, will be provided by firm.

Electricity, M.S Sheet 4.5mm, Crane, Lifter will be provided by JPCL Jamshoro.

Nete:- D.D/Pay order amounting to Rs. 800/- or D.R Amounting to Rs. 500/- in favour of R.E(M) TPS, Jamshoro may be attached at the time of submission of bid in a separate envelop mentioning the name of firm and subject.

Eligibility of Contractor

The Contractor/firm having experience of same type of job and should be registered with Pakistan Engineering Council (PEC), in the field of Mechanical

The firm must be registered with FBR, having NTN active tax payer. Also registered wth Sindh Revenue Board (SRB