



JAMSHORO POWER COMPANY LIMITED.

OFFICE OF THE
CHIEF EXECUTIVE OFFICER
JPCL JAMSHORO.

NO.CEO/RE(O)/CIVIL/ 3610-13

Dated:- 29 / 04 /2022.

1. M/S Bismillah Engineering Works Office # 315 Area 48/H Haq Bahoo Town Korangi No. 1 Karachi
2. M/S P.C Chawala & Co, House No. E-191 Gulstan-e-sajjad, Qasimabad Hyderabad
3. M/S S.S Constructors & Traders London Town Shop No. 03 near by Al Rehman Hotel, Main Sehwan Road Jamshoro
4. M/S Techno-Pak Construction Co, H. A #4/09 Mehran University Housing Society District Jamshoro

QUOTATION

SUBJECT: CONSTRUCTION OF DRAIN CHANNEL IN MAIN GATE FROM BUNGALOW NO. B-09 TO B-14 CLEANING OF SEWERAGE WELL AT RESIDENTIAL COLONY TPS JAMSHORO

Quotations for the above subject work are hereby invited from your company/ firm on percentage rate basis on the following terms and conditions.

SR.No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Dismantling cement concrete plain 1:4:8	Cum	22.94	1095.60	25133.06
2	Excavation in shingle or gravel formation and rocknot requiring blasting underdressed lead upto 50 mtr (a) Dry	Cum	17.84	380.40	6786.34
3	Cement concrete plain i/c placing compacting finishing and curing complete (i/c screaning and washing of stone aggregate) without shuttering Ration 1:4:8	Cum	5.95	4824.94	28708.39
4	Bricks work other then building i/c striking of joints Pto 3.0 mtr height in cement sand mortar Ratio 1:5	Cum	11.47	6792.03	77904.58
5	Cement plaster 1:4 13mm thick	Sqm	75.28	203.67	15332.28
6	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening of washing stone aggregate without shuttering Ratio 1:2:4	Cum	0.59	6343.62	3742.74
7	Carriage of 3.00 cum or 5matick tons of all material like earth steel sand stone aggregated spawl, caol, lime etc laid upto 02km	Cum	40.78	137.75	5617.45
8	Providing lowering in to trenches & jointing cement concrete reinforced pipe in line to correct alignment and gride i/cutting of pices where necessary cost of jointing material and testing with internal diameter (d) 200mm dia	Rm	12.00	832.43	9989.16
9	Making and fixing grating in opening i/c fixing at stie with flat iron 50x10mm and 20mm squire bar at 100mm c/c	Sqm	39.03	6899.60	269291.39
10	Earthe excavation in ashes, sand and soft soil or silt clearance underdressed upto 30 mtrs	Cum	180.00	109.98	19796.40
Total Rs.					4,62,302.00

Add: Contractor Premium _____ % above/below Rs. _____

Total Rs. _____


(Cont:P-2)

SPECIAL CONDITIONS

- 01- The Quotation shall be received on 17-5-22 at 12:40 in Tender / Quotation box at office of CE/TD and Opened at 12:30 on same date in presence of the bidders, in same office.
- 02- The Quotation may either be sent by mail or deposited in the tender / Quotation box kept for the purpose in the office of the CE/TD before due date and time for opening as above.
- 03- The Quotation received with overwriting/cutting/mutilate and having doubtful figures will be rejected.
- 04- The envelop containing the quotation shall be addressed to this office should be written following on the top face of the envelop.

ENQUIRY**DUE FOR OPENING ON**

- 05- The work shall be carried out according to the standard design and specification on the instruction of the Engineer Incharge.
- 06- The Payment will only be made for the work carried out according to the standard applicable Specifications and satisfaction of the Engineer Incharge. The under specification of work and material shall be rejected and will have to remove/replace by the contractor on his risk and cost.
- 07- The procuring agency may reject all bids or proposals at any time prior to the acceptance of a bid or proposal. The procuring agency shall upon request communicate to any supplier or contractor who submitted a bid or proposal, the grounds for its rejection of all bids or proposals, but is not required to justify those grounds.
- 08- In case Government announce any public holiday OR due to unavoidable circumstances the Quotation will be opened on next working day
- 09- Copy of renewed PEC (Civil), Active NTN & SRB Certificate should be attached
- 10- Time of completion is 15 Days from the date receipt of Engineer order to commence the work.
- 11- The D.R of Rs. 500/= Must be attached with Quotation at the time of participation.
- 12- No bill will be entertained till submission of SRB invoice by the Contractor.
- 13- Stamp duty at 0.35% on contract price may be paid by contractor postage stamps may be affixed on work order before processing the bill


 29/4/22
 Resident Engineer (O)
 (GENCO-I) JPCL, Jamshoro.

Cc.to:

1. Chief Executive Officer, JPCL Jamshoro.
2. C.F.O, JPCL Jamshoro.
3. Executive Engineer (Civil) TPS, Jamshoro.
4. Notice Board.